

Marquette Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>17</u> T. <u>45</u> N. S., R. <u>26</u> E. W.		<u>E-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>17</u> T. <u>45</u> N. S., R. <u>26</u> E. W.		<u>7, 14-A</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Rabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 18 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- E-6 - East $\frac{1}{4}$ corner - Section 17; Wood post, Maple 14 - N39°W - 35 lks.; W. Birch 10 - S50°E - 22 lks.
 - 7 - North 1/16 corner on the East section line - Sec. 17; not previously established.
 - 14-A- Witness corner to S. 1/16 corner on the East section line - Sec. 17; not previously established.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- E-6 - Set M.P.O.L. between the NE and SE section corners of Sec. 17. Fits G.L.O. calls to ridge and lake south. M.P.O.L. position was used by Gourdie Frazer Assoc. of Marquette for survey in Sec. 16. Found 1 $\frac{1}{2}$ " pipe 47.44' N26°E from this $\frac{1}{4}$ corner, but it is not of record and does not fit G.L.O. feature calls.
 - 7 - Set M.P.O.L. between the East $\frac{1}{4}$ corner and the NE section corner of Section 17.
 - 14-A- Set on the East section line of Sec. 17 - 193.3' north of the S. 1/16 corner. South 1/16 corner falls in a small lake.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL - 1" pipe, 4" aluminum cap
- E-6 - 10" Oak - S70°W - 13.2'; 6" W. Birch - N37°W - 12.8'; 2" R. Pine (no marks) - N55°E - 15.2'; 6" Oak - S76°E - 13.0'; 1 $\frac{1}{2}$ " pipe buried - N26°E - 47.44'.
 - 7 - D.N.R. Monument buried in road; 10" Oak - S9°W - 34.4'; 6" W. Birch - N62°W - 20.2'; 9" W. Birch - N18°E - 34.0'; 5" W. Pine - N68°E - 19.75'.
 - 14-A- S.W. corner basement wall - N59°W - 68.1'; 13" W. Pine - N83°E - 48.3'; 10" R. Pine - N 16°E - 41.0'; 16" W. Pine - S86°W - 70.0' measured to center of tree (not marked).

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Rabbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 6-25-79 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558