

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S., R. 26 E. W.	D-9 & F-9
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- D-9 - North 1/4 corner of Section 29; Cons. Dept. Mon. - 1" pipe with 4" brass cap set by Dean C. Delamater Nov. 1, 1951. No witness trees available.
  - F-9 - North 1/4 corner of Section 28; Cons. Dept. Mon., 1" pipe with 4" brass cap set by Dean C. Delamater R.L.S. Nov. 1, 1951, N.B.T. 30" W. Pine stump S20°W - 41 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- D-9 - Witnessed Mon. as set by Dean C. Delamater R.L.S. in 1951.
  - F-9 - Witnessed Mon. as set by Dean C. Delamater R.L.S. in 1951. Remains of Delamater's "30" W.P. stp. NBT" in place but in very poor condition.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- D-9 - Brass Cap Cons. Dept. Mon.; Brass tag (RLS 17618) in 8" Spruce - N88°E - 109.5'; 5" Spruce - N79°E - 107.6'; 3" Balsam - N53°E - 101.3'; 5" Aspen - S19°E - 79.0'.
  - F-9 - Brass Cap Cons. Dept. Mon.; 6" Spruce - S36W - 106.7'; 3" W. Pine - N23°E - 77.3'; 6" R. Oak - N75°E - 46.4'; 7" W. Birch - S24°E - 25.5'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:  
SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_