

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45N</u> N. S., R. <u>26W</u> E. W.	<u>C-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 28, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

S.E. Sec. Cor. of Sec. 19

Michigan Department of Conservation Mon.

1" pipe w/4" Br. Cap

Set 10-23-51

8" aspen-N 43°E- 46 Lks.

10" aspen-S 58°E- 71 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" pipe with old sq. scribed post on ground nearby. Both 1951 N.B.T.s are down and very rotten. It appears that the Cons. Dept. Mon. either was never set or it was destroyed during a wildlife cutting project in 1975, and the 3/4" pipe set in its place. Set D.N.R. Mon. in place of 3/4" pipe. Aspen N.B.T.'s were not blazed but were scribed in their bark.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Scribed in bark.

4" aspen - N32° E - 5.6'	D.N.R. Mon.
3" aspen - N52° W - 11.1'	
4" aspen - S58° E - 17.8'	
3" J. pine - S46° W - 12.8'	

SIGNED BY _____

David B. Babbitt

DATE _____

9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: _____