

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>45N</u> N. S., R. <u>26W</u> E. W.	<u>G-9</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 29, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

SE Sec. Cor. of Sec. 21	Mich. Cons. Dept. Mon.
Original Govt. Survey - 1852	1" pipe w/4" brass cap
Wood post	Set 11-1-51
WP 30"-N59°W-62 Lks.	One original B.T. in place-good condition.
Hem. 30"-S72E-31 Lks.	12" aspen-S40W-46 Lks.
	34" white pine stp.-N18E-61 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" pipe w/4" brass cap. 34" W.P. stp. - N18°E-61 Lks. is in good condition. Stp of 12" aspen, S40°W-46 Lks. is in place but very rotten. Stp. of w. pine OBT is in place N59W - 62 Lks. but in poor condition. Re-witnessed Mon. as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Brass capped Cons. Dept. Mon.
 9" w. pine - N2°E - 11.4'
 14" w. birch - S2°W - 29.25'
 6" maple - S67°E - 6.7'
 7" balsam - S63°W - 15.2'
 30"± w.p. STP (OBT) - N59°W - 40.9'

SIGNED BY David B. Babbitt DATE 9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)