

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

(County)	Located In:	Corner Code -#
1. Public Land Survey	T 45N R 26W	C3
	T R	D3
	T R	
	T R	
2. Property Controlling in Section	S 5 T R	15
	S T R	16
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on April 24, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3			•	•	•								
4													
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

C3	D3	15	16
Southwest corner of Section 5. 1951 Delameter - set 1" iron pipe with 4" brass cap. MBTs 16" v. pine S67 E 100 lks., 12" spruce S63W 65 lks.	Quareter corner common to Sections 5 and 8 wood post, 1852. M.M. Hall, D.S. Spruce 10 N24W 26 lks., tamarack 14 S44E 22 lks. Monument and accessories not found.	West one-sixteenth corner common to Sections 5 and 8. Not set on original survey nor subsequently, apparently.	East one-sixteenth corner common to Sections 5 and 8. Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C3	D3	15	16
Found monument as described, revitnessed as found.	Established midway and on line.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C3	D3	15	16
Dept. of Conservation monument.	DNR monument.	DNR monument.	DNR monument.
8" spruce N53E 35.3'	8" tamarack N31E 12.8'	5" tamarack S35E 19.0'	4" tamarack S24E 40.5'
8" spruce S69E 17.55'	8" tamarack S32E 25.9'	5" spruce S06E 74.85'	4" tamarack S05E 34.5'
6" spruce S69E 17.55'	8" tamarack S72W 6.5'	30" white pine S69W 91.1'	3" spruce S23W 28.5'
6" white pine S24W 32.85'	8" tamarack N39W 13.1'	Squared wood post N35E 0.5'	Squared wood post North 0.85'
6" spruce N71W 9.5'			

Signed by Keith L. Sackett Date _____
 Surveyor's Michigan License No. 19006

