

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
(County)

Located In: _____ Corner Code *##*

1. Public Land Survey	T <u>45N</u> R <u>26W</u>	<u>L5</u>
	T _____ R _____	<u>L6</u>
	T _____ R _____	<u>M5</u>
	T _____ R _____	<u>M6</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on April 29, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	14	17	16	15	14							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L5 One quarter corner common to Sections 12 and 13. Wood post, 1852, W.K. Hall D.S. Maple 8 W52W 20 Lks, Yellow birch 16 S50E 35 Lks. Monument and accessories not found.	L6 Center quarter corner of section 13. 1990, A. Pearce. Found and accepted 1" iron pin and established witnesses. Found 1" iron pine and rejected it. Iron pin is 14.44' southwesterly of intersection of quarter lines.	M5 Northeast corner of Section 13. 1951 Delameter - monument not described, NBTs 8" red oak N07W 42 Lks., 5" soft maple S40E 4 Lks. Monument and accessories not found.	M6 Quarter corner common to Sections 13 and 18. Wood post, 1844, W.A. Burt, D.S. Sugar 8 S34E 8 Lks, Yellow birch 14 N36W 32 Lks. Monument and accessories not found.
---	---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L5 Restored midway and on line.	L6 Established at the intersection of the north-south and east-west quarter lines of Section 13.	M5 Restored by single proportionate measure between the section corner one mile south and the township corner two miles north.	M6 Restored midway and on line.
---	--	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L5 DNR monument. 4" green ash N39E 17.55' 15" red oak S21E 29.8' 6" green ash S70W 5.5' 4" red maple N17W 24.8'	L6 DNR monument. 14" jack pine N32E 27.1' 9" jack pine S16E 25.7' 8" jack pine S63W 48.3' 7" jack pine N63W 53.2' Wood post SE 0.5'	M5 DNR monument. 5" red oak N03E 25.3' 5" red maple N83E 14.0' 5" sugar S04E 13.2' 5" sugar S81W 30.45' Squared maple S75E 0.9'	M6 DNR monument. 8" sugar maple N20E 24.65' 8" red maple S73E 8.85' 6" red maple S46W 12.1' 7" sugar maple N39W 5.1'
---	--	--	--

Signed by Keith Sackett Date _____
 Surveyor's Michigan License No. _____ 19006 _____

