

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

	Located In:	Corner Code -#
1. Public Land Survey	T 45N R 26W	F3
	T _____ R _____	G3
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S 4 T R	15
	S T R	16
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on April 9, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

F3	G3	15	16
Quarter corner common to Sections 4 and 9. Wood post, 1 1/2" N.W. Wall, D.S. White pine 20 N60E 90 Lks, Tamarack 16 S31W 69 Lks. Monument and accessories not found.	Southeast corner of Section 4. 1973 F.J. Bray - Set 1" iron pipe with 4" brass cap NBTs 11" white pine N47E 54.1', 16" white pine S37E 32.0'	West one-sixteen corner common to Sections 4 and 9. Not set on original survey, no evidence of subsequent establishment.	East one-sixteenth corner common to Sections 4 and 9. Not set on original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F3	G3	15	16
Restored midway and on line.	Found monument as described, revitnessed as found.	Restored midway and on line.	Restored midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F3	G3	15	16
DNR monument. 9" spruce N25E 10.7' 5" spruce S77E 15.6' 5" spruce S20W 4.8' 16" white pine N21W 10.5' 4" squared spruce N65W 3.6'	1" iron pipe w/4" brass cap 20" white pine N63E 50.8' 12" white pine S88E 38.2' *20" white pine S35E 32.1' 8" jack pine N33W 76.6'	DNR monument. 6" white pine N61E 16.65' 4" white pine S58E 27.25' 8" red maple S60W 36.7' 5" white pine N62W 29.85'	DNR monument. 12" jack pine N57W 6.7' 14" jack pine N74E 33.1' 7" jack pine S13W 16.1' 4" spruce S42E 26.9'

*Existing NBT.

Signed by Keith L. Sackett Date _____

Surveyor's Michigan License No. _____ 19006

