

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

	(County)	Located In:	Corner Code #/
1. Public Land Survey	T 45N R 26W		E2
	T ___ R ___		E1
	T ___ R ___		I1
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on April 10, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E2	E1	I1
Quarter corner common to Sections 4 and 5. Wood post, 1852. N.N. Hall, D.S. White pine 16 N39W 48Lks, White birch 10 S30E 51 Lks. Monument and accessories not found.	Northeast corner of Section 5.	Northeast corner of Section 3.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E2	E1	I1
Restored by single proportionate measure between the northeast and southeast corners of Section 5.	FD existing DWR monument.	Replaced existing DWR monument under water with longer DWR monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E2	E1	I1
DWR monument. 5" white pine S04W 74.4' 7" jack pine S22W 52.4' 14" aspen S45E 14.65' 5" spruce N03W 28.45' 3" squared aspen S15W 1.4'	Dept. of Conservation monument. 6" white birch N40E 22.9' 6" maple S55E 23.1' *24" white pine S59W 28.4' *8" white pine N08W 20.0'	DWR monument. 10" jack pine S43E 88.9' *10" jack pine S22E 56.2' Power pole S27W 66.0' SE cor bridge abutment N39W 164.2'

*Existing MBT.

*Existing MBT.

Signed by Keith Sackett Date June 13, 1991

Surveyor's Michigan License No. 19006

