

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<b>T</b> <u>Marquette</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T 45N R 26W	G2
	T R	G1
	T R	
	T R	
2. Property Controlling in Section	S 4 T R	7
	S T R	14
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on April 11, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G2	G1	7	14
Quarter corner common to Sections 3 and 4. Wood post, 1852. N.H. Hall, D.S. Sugar 14, N30W, 41 Lks., spruce 8, S43E, 33 Lks., monument and accessories not found.	Northeast corner of Section 4.	North one-sixteenth corner common to Sections 3 and 4. Not set on original survey nor evidence of subsequent establishment.	South one-sixteenth corner common to Sections 3 and 4. Not set on original survey nor evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G2	G1	7	14
Restored by single proportionate measure between the northeast and southeast corners of Section 4. Monument driven parallel to bedrock.	Found existing DNR monument.	Established by single proportionate measure between the northeast and east quarter corners of Section 4.	Set midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G2	G1	7	14
DNR monument. 8" white pine N35E 21.0' 6" white pine S65E 31.7' 8" red maple S67W 23.8' 8" white pine N55W 4.9' 4" squared maple N30E 6'	Dept. of Conservation monument. *14" white pine N30E 2.65' 6" white pine S13E 29.0' 10" red oak S36W 29.6' *6" sugar maple N63W 7.5'	DNR monument. 8" balsam N35E 10.7' 6" balsam S58E 17.2' 30" white pine S39W 37.4' 8" white birch N38W 16.3'	DNR monument. 9" white pine N17E 20.8' 8" white pine S53E 10.1' 6" white pine S69W 3.1' 4" white pine N24W 20.6'

\*Existing NBY's.

Signed by Keith L. Sackett Date \_\_\_\_\_

Surveyor's Michigan License No. 19006

