

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>45</u> N. <u>26</u> R. <u>W.</u>	<u>G-3</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 18 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-3 Woodpost:

W. Pine 26 N23°W 72 links
W. Pine 26 S41°E 43 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

This corner was set from the stump bottoms of two probable original witnesses. Conforms well to features north, south and west and probable line tree stump east. Corner lies on west edge of small opening with cabin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing-magnetic. Corner monument: 1" pipe with 4" brass cap.

11" W. Pine (83 MBT) N47°E 54.1'
16" W. Pine (810 MBT) S37°E 32.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 11-1-73
MICHIGAN SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575