

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 27 W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 16-17-20-21

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/14/65

WITNESSES TO CORNER..... 9" Red Oak (S21 NBT), S 77° E 04 1/2 lks.



8" Red Oak (S16 NBT), N 18° E, 33 lks.

8" Red Oak (S20 NBT), S 83° W, 61 lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two (probable) Pine bearing trees, both are Pine Stumps lying in proper position. Position checks with corners to East and West.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4/29/1966  
REGISTERED LAND SURVEYOR