

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45N N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER 1/2 corner bet. Secs. 20-21

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10/19/66

WITNESSES TO CORNER..... 9" Cedar (1/2 S NBT) N8°W 12.0'



9" Tamarack (1/2 S NBT) S57°E 30.2'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner re-established midway and on line bet. two sec. cors.  
Found a cedar stump bottom, bearing N59 W 12 lks., a possible  
bearing tree.

Corner lies 10 lks. north of a stream.

**SURVEYOR'S SEAL**

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 1/11/67  
REGISTERED LAND SURVEYOR