

✓

**MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION**

LAND CORNER RECORD

T. 45N N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER West 1/16 Corner bet. Secs. 19-30

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8/4/66

WITNESSES TO CORNER..... 13" jack pine (W1/16 BT) N46°E 22.2'



13" jack pine (W1/16 BT) S10°E 22.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed on line bet. sec. cor. to west and 1/4 corner to east and by single proportionate measure.

Corner lies 2.00 ch. east of a cutting edge.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 1/10/67
REGISTERED LAND SURVEYOR