

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 corner bet. Secs. 26-35

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9/14/66

WITNESSES TO CORNER..... 6" Soft Maple (1/4 S NBT) S81°E 17.2'



5" Jack Pine (1/4 S NBT) S15°W 26.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original B.T.; a w.pine, bearing N45°W, 31 lks., a stump with bottom of face and notch in evidence.

Corner lies on west margin of a Game Division Habitat Improvement clearing.

Note:

Record notes indicate this B.T. to be a "W.Birch". We find it a "W.Pine."

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1/11/67  
REGISTERED LAND SURVEYOR