

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 45 N.R. 27-28 W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 7-18-12-13

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 12-11-63

WITNESSES TO CORNER..... 10" Red Pine (S 13 NBT) S 14° W 128½ links



14" Red Pine (S 18 NBT) S 22° E 132½ links

13" Red Pine (S 7 NBT) N 1° E 277½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from one Y. Pine B.T. Bearing S 30° E, 73 links.
Stub is burned but find marks in excellent condition.

Corner lies in water, in a flooded Beaver Dam.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 27, 1964
REGISTERED LAND SURVEYOR
Billy D. Buckler