

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 45-46 N.R. 27W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 5-6-31-32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/1/64

WITNESSES TO CORNER..... 12" Soft Maple (S6 NBT) S58°W 42 Lks.



11" Hard Maple (S5 NBT) S28°E 54 Lks.

12" Hard Maple (S32 NBT) N61°E 35 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at a Wood Post set by unknown person. Position checks with Corners both East and West. Found a down and rotted Y. Birch bearing S77°E 29 Links for a possible Bearing Tree.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED BILLY D. BUCKLER DATE 8/4/1964
REGISTERED LAND SURVEYOR