

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 27 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 35 and 36

CORNER MONUMENT 1-inch iron pipe with 4-inch brass cap

DATE MONUMENT PLACED AND WITNESSED September 12, 1961

WITNESSES TO CORNER..... Cedar 10" S21 E 42.5 links



Cedar 6" N50 W 17.0 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was set from one original cedar BT (N35W 8links). The tree had fallen down but had been chopped through, leaving a high stump and the stump re-erected and braced, about 10 to 20 years ago, by some unknown surveyor. A small part of the scribe marks were still distinguishable on the upper face. Four posts, two of which were old, stood within four feet of the proper location - one was properly located. The other cedar B.T. was completely decayed, except for some roots in the ground. Corner was located and reported by A. Enger, Assistant District Forester in December, 1957.

SURVEYOR'S SEAL

SIGNED *Ann A. Metts* DATE Sept 13, 1961
REGISTERED LAND SURVEYOR