

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 26 & 27 W.


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 1 & 2 Secs. 7

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 12-14-62

WITNESSES TO CORNER..... 4" Maple (N.B.T.) (6), N. 61° E., 39 Lks.



7" Jack Pine (N.B.T.) (S. 12), S. 27° W., 86 Lks.

10" W. Birch (N.B.T.) (S. 1), N. 55° W., 40 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by placing on line and single proportioned measurement between section corners 1 mile to the north and south. Blazes on stump in vicinity. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 3/4/65
REGISTERED LAND SURVEYOR