

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44-45 N. R. 27W


Marquette-Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 4-5-32-33

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/30/63 with Russell Hinds

WITNESSES TO CORNER..... 10" Tamarack (S5 NBT) S35° W 32 Lks.



6" Tamarack (S32 NBT) N 63° W 25 1/2 Lks.

7" Twin Tamarack (S4 NBT) S 64° E 33 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure along Township line.
Found no evidence of Original Corner.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED BILLY D. BUCKLER DATE 7/29/1964
REGISTERED LAND SURVEYOR