

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 27. W. . .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 8. -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap. -----

WITNESSES TO CORNER 2" Red Oak S 67 W 25 Links -----  
marked  $\frac{1}{4}$  S NBT

8" Red Oak (clump) N 36 E 69 Links -----  
marked  $\frac{1}{4}$  S NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from one Y. Pine B.T. Bearing S 18 E, 47 links. Stump cut. Found face, Notch and scribe marks "B.T." in very good condition.

Corner found by H. F. Wardwell, Northwoods Club, Ishpeming.

Corner placed with H. F. Hardwell and C. Schooley, Dist. Forester.

Placed location poster 5 chains East on road.

Corner placed and witnessed on 9 May 1958.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 4-15-59  
REGISTERED LAND SURVEYOR