

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

(County)

Located In:

Corner Code 11

- | | | |
|---------------------------------------|-----------------------------|--------------------|
| 1. Public Land Survey | T <u>45N</u> R <u>27W</u> | <u>L9</u> |
| | T _____ R _____ | <u>L11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S <u>25</u> T _____ R _____ | <u>10</u> |
| | S _____ T _____ R _____ | <u>MC between</u> |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | <u>11 & 15</u> |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith Sackett, in a field survey on December 28, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|---|--|---|---|
| <u>L9</u>
Original monument and accessories not found. | <u>L11</u>
Original monument and accessories not found. | <u>10</u>
Found Michigan Dept. of Nat. Resources monument reported to have been set midway and on line between corners north and south. It was not midway and on line. | <u>MC</u>
Not set on original survey nor subsequently, apparently. |
|---|--|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|---|---|---|--|
| <u>L9</u>
Restored midway and on line. | <u>L11</u>
Found Michigan Dept. of Natural Resources monument set by registered land surveyor Billy D. Buckler on 1-11-67. Corner covered with fill and NBT's removed. | <u>10</u>
Restored midway and on line between corners north and south. | <u>MC</u>
Established during section subdivision. |
|---|---|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|---|---|--|---|
| <u>L9</u>
Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
7" maple S60E 27.5' 1/4s, NBT
4" maple N35W 10.0' 1/4s, NBT
7" maple S09W 40.5' 1/4s, NBT | <u>L11</u>
Restored at M.D.N.R. monument. SE corner camp N01E 5.87'
8" cedar S55E 8.38 nail and tab
NW corner sauna south 31.27' | <u>10</u>
Set 1" I.D. x 36" iron pipe with plastic cap.
7" maple S75E 28.0' 1/16s, BT
3" oak N80W 39.9' 1/16s, BT
3" oak N25W 26.7' 1/16s, BT
2" oak N11E 21.3' 1/16s, BT | <u>MC</u>
Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
4" red pine N65E 9.8' MC, BT
16" red pine N18E 6.0' MC, BT
7" maple S23E 20.8' MC, BT |
|---|---|--|---|

Signed by Keith Sackett

Date January 16, 1991

Surveyor's Michigan License No. 19006