

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette (County) Located in: Corner Code #
1. Public Land Survey T 45N R 27W K6
T 45N R 27W L7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Aug 06 1997

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a dot in cell (6, K).

A. Description of original monument and accessories and/or subsequent restoration:
(K6) Quarter corner common to Sections 13 and 14. 1967: Billy Buckler, RLS MDNR. Set DNR monument from original evidence witnessed by 11" R.Oak N09W 44.3' and 5" Soft Maple S80E 22.4'.
(L7) Quarter corner common to Sections 13 and 24. 1957: Billy Buckler, RLS, MDNR. Found 3/4" iron bar set by Marquette Co. Rd. Commission from original evidence witnessed by Y.Pine OBT N26E 8 lks.; 10" J.Pine NBT S71W 65 lks.; marked an additional witness 9" R.Pine S86E 133 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(K6) Found monument and witnesses as described. Both NBT's are alive and standing in excellent condition with both faces closed. W.Pine OBT is still evident as a stump but no markings are visible. Monument was rewitnessed as found and is accepted as a careful and faithful PERPETUATION of the position of the original corner.
(L7) Found monument and witnesses as described. Both NBT's are live and standing in excellent condition with both faces closed. Remains of OBT still in place in very poor condition with no marks visible. Monument was rewitnessed as found and is accepted as a careful and faithful PERPETUATION of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(K6) DNR monument (L7) 3/4" iron bar
06" R.Maple N32E 54.8' (1/4S,NBT) 11" J.Pine N45E 27.4' (1/4S,NBT)
06" R.Maple\* S70E 22.4' (1/4S,NBT) 20" R.Pine\* S71E 88.9' (1/4S,NBT)
08" R.Maple S41W 31.7' (1/4S,NBT) 16" J.Pine\* S88W 42.8' (T45NR27WS24)
16" Oak\* N01E 44.1' (1/4S,NBT) 08" R.Maple N12W 13.8' (1/4S,NBT)
\* denotes existing NBT. All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette Date
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division