

107

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Marquette (County) Located In: Corner Code #
1. Public Land Survey T 45N R 27W L5
T 45N R 27W M6
2. Property Controlling In Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims
M6 Aug 12 1997
L5 Aug 18 1997

Grid table with columns A-M and rows 1-13. Contains numerical data for sections 1-36.

I, Paul R. Bressette, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (L5) Quarter corner common to Sections 12 and 13. 1966: Billy Buckler, RLS, MDNR. Set DNR monument on line between Section corners and record distance east of swamp edge witnessed by 8" Hard Maple N65W 38.3' and 8" B. Spruce N40E 6.3'.
(M6) Quarter corner common to Sections 13 and 18. 1954: DeLaMater, RLS, MDNR. Set 1" iron pipe with 4" brass cap mid-point and on-line between section corners witnessed by 5" R.Pine West 15 lks. and 7" B.Spruce S72E 35 1/2 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (L5) Found monument and maple witness as described. Maple is live and standing in excellent condition with both faces closed. No evidence of spruce observed. Monument was re-witnessed as found and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.
(M6) Found monument and witnesses as described. R.Pine is 17" in diameter, live and standing in excellent condition with both faces closed. Spruce is dead and down with both faces visible. Monument was re-witnessed as found and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (L5) DNR monument (M6) 1" iron pipe w/ 4" brass cap
11" B.Spruce N04W 16.1' (1/4S,NBT) 08" B.Spruce S72E 32.75' (1/4S,NBT)
05" B.Spruce N82E 28.8' (1/4S,NBT) 10" W.Pine S01W 36.4' (1/4S,NBT)
10" B.Spruce S29W 15.95' (1/4S,NBT) 17" R.Pine * N80W 9.9' (1/4S,NBT)
11" Maple * N54W 39.4' (1/4S,NBT) 14" R.Pine N28E 23.3' (1/4S,NBT)
* denotes existing NBT. All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette Date
Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division