

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette  
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>27W</u>	MC <u>H13-113</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 09 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


**A. Description of original monument and accessories and/or subsequent restoration:**  
 (MC H13-113) Meander corner on Township line on west side of Kates Lake. Remonumented in the original position from original W.Pine BT and recorded in 1957 by Billy O. Buckler, RLS. 1" pipe with 4" brass cap. 16" Soft Maple S13E 62 links, 13" Tamarack N66W 78 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(MC H13-113) Recovered the 1957 monument as described, in good condition, projecting about 2'a.g., and at record bearing and distance from the remains of the original W.Pine BT, found N44W 27.9', being a stump with "BT" and notch plain, and from the 1957 witnesses: the maple a dead stub and the tamarack in good condition with overgrown blaze. Left the monument in place and made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(MC H13-113) Fd. 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:  
 7" Balsam N33E 2.8' "MC NBT"  
 7" Balsam S19E 32.3' do  
 8" B.Spruce N16W 40.9' do  
 16" Tam. N56W 50.8' (the 1957 NBT)  
 Sq'd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/8/01

For the Michigan Department of Natural Resources - Forest Management Division