

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>45N</u> R <u>27W</u>	<u>PCC 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/24/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(PCC 1) - Property Controlling Corner on the N-S 1/4 line of Section 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(PCC 1) Established the corner on a straight line between the South 1/4 corner of Section 24 1250.00' south and the North 1/4 corner of Section 24 4018.70' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(PCC1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap stamped "45N 27W N-S 1/4 line Sec 24 12+50 north PS33986 8-24-10".  
 Set measuring nail with MDNR tag in the side of:  
 3" J.Pine N18E 25.3' mrkd "POL BT"  
 3" J.Pine N74E 15.5' do  
 3" W.Pine S35E 36.9' do  
 2" Poplar S52W 11.5' mrkd " X X "  
 Sq'd cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/30/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division