

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 28-29 W.

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 30, 24, 25

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Jack Pine N 42° W 60½ links to notch

12" Jack Pine N 56° E 61 links to notch

10" Jack Pine S 27° E 87 links to notch

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one Yellow Pine B.T. in place, stump badly burned with notch very plain.

Distance check good to marsh West, to lake South.

Traces of stake very plain in soil.

Corner found by Forestry Division survey crew while making a partial re-survey of this area.

Corner placed and witnessed August 9, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/17/56
REGISTERED LAND SURVEYOR