

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T.45.. NR.28-29.W

----- Marquette Co. ----- COUNTY

DESCRIPTION OF CORNER .. Section Corner common to Sections 25, 36, 30, 31

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap -----

WITNESSES TO CORNER 6" Soft Maple S 23° W 31 links -----

9" Aspen N 27° E 44 links -----

7" W. Birch S 74° E 38½ links -----

1" Steel Pin West 19 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double proportionate measure to corners all four directions:

1/4 Corner	1/2 mile	North
1/4 Corner	1/2 mile	East
Section Corner	1 mile	West
1/4 Corner	1-½ mile	South

Found steel pin set for Section Corner 19 links West. Set about 2 years ago.

No evidence of original Corner.

Corner placed and witnessed September 25, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 10/18/56  
REGISTERED LAND SURVEYOR