

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 28 W. .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 30 and 31 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 10" Jack Pine ----- S 44° W ----- 62 links -----

6" W. Pine ----- S 5° E ----- 56½ links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two White Pine stumps, both at proper bearing and distance, probable B.T.'s; badly burned and rotted.

Possible traces of stake in soil. Found an old Yellow Pine stub blazed on East and West sides East of this corner.

Corner placed and witnessed August 17, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/4/56
REGISTERED LAND SURVEYOR