

J

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 NR 28 W

Marquette

COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 26 and 27

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER Black spruce 7" N 30 W 17 links, marked 1/4 S NBT

Black spruce 7" S 26 W 15 1/2 links, marked 1/4 S NBT

Distances measured from center of brass cap to NBT notch

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one original spruce bearing tree in good condition. Scribe marks plain. Tamarack stump in place with no identifying marks. Wood post in place.

Corner was found while cruising timber in this area.

Corner was placed and witnessed on 29 May 1957 with Clayton Schooley, District Forester, Michigamme State Forest, Ishpeming, Michigan.

SURVEYORS SEAL

Henry S. Peterson

SIGNED Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE 5/31/57