

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 45&46 NR 28&29W

M a r q u e t t e COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6, 1, 36, 31,
Also township corner.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 9" J. Pine (S 31 NBT) N 40° E 23 Links

9" J. Pine (S 6 NBT) S 70° E 14 Links

12" J. Pine (S 1 NBT) S 86° W 14 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was re-established by double proportionate measure from
corners: 1 Mile North; 1 Mile West; 1/2 Mile South; 1/2 Mile East.
Corner lies 1/2 chain South of road.

Corner was placed and witnessed September 28, 1959 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 4/11/60