

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N. R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ Corner for sections 28-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-13-61

WITNESSES TO CORNER..... 9" Cedar ($\frac{1}{4}$ S NBT) N75°E 37 links



5" Cedar " " N64°W 48 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established midway and on line between two section corners. Found old cedar squared 21 links east and 15 links north of $\frac{1}{4}$ corner. No other evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler