

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45N R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER Section corner for sections 27-28-33-34

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10-30-61 with Frank J. Bray

WITNESSES TO CORNER..... 12" Cedar (S34 NBT) S20°E 61½ links



9"H. Maple (S28 NBT) N24°W 43 links

9" S. Maple (S27 NBT) N75°E 96 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at old down wood post found by survey crew. Found a cruisers "Register Tree" at corner bearing names of: Alex Peterson and Russell Sillers 5/25/23.

Found cedar tree (down) which may be an original line tree. Also found a tamarack (possible line tree) to North. Position of corner fits calls of notes to stream to north; swamp edges south and east.

Found numerous blazes along line to west of corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler