

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER Section corner for Sections 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-13-61

WITNESSES TO CORNER..... 7" Tamarack (S28NBT) N31°E 15 links



6" Tamarack (S33NBT) S58°E 28 links

4" Balsam (S32 NBT) S60°W 08 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established at intersection of old blazed lines to east, west and south. Position of ledge 2.25 chs. south agrees with calls of notes. Several swamp edges and a stream to south also check well.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler