

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45 N.R. 28 W


Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Secs. 19-20-30-29

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6/16/64 with Arthur Klawiter

WITNESSES TO CORNER..... 5" Red Oak (S 19 MBT) N 28° W 28 lks.



CIRCLE CORNER REGISTERED

10" White Pine (S30 MBT) S22° W 16.5 lks.

9" White Pine (S20 MBT) N76° E 70 lks.

AND

Corner lies in North margin of small swamp.

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was replaced from one Yellow Pine Stump bearing N69° W 64 lks. and Yellow Pine Stump bearing N21° E 94 lks. Position checks with good corners  $\frac{1}{2}$  mile North and South.

**SURVEYOR'S SEAL**

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 7/29/1964  
REGISTERED LAND SURVEYOR