

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 19-20

CORNER MONUMENT 1" Iron Pipe with Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4/17/64

WITNESSES TO CORNER..... 11" White Birch ($\frac{1}{4}$ S NBT) N50° E 14 $\frac{1}{2}$ Lks.



5" Soft Maple ($\frac{1}{4}$ S NBT) S3° W 35 $\frac{1}{2}$ Lks

4" Soft Maple ($\frac{1}{4}$ S NBT) S62° W 17 $\frac{1}{2}$ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from remains of two Original Bearing trees; a Yellow Pine Stump N 40° W 17 Links, with notch and burnt out blazes in proper position and a Yellow Pine Stump, fallen down, S66° E 21 Links with old face and axe marks. No evidence of recent use.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 7/29/1964
REGISTERED LAND SURVEYOR