

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N. R. 28^W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 1 34-35

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/11/64 with Frank Bray, Registered Land Surveyor

WITNESSES TO CORNER..... 8" Cedar ($\frac{1}{4}$ SMBT) N70° W 20 lks.



8" Cedar ($\frac{1}{4}$ S NBT) S87° E 33 lks.

12" White Pine ($\frac{1}{4}$ SMBT) S3° W 55 $\frac{1}{2}$ lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two original Cedar Witnesses; bearing N80° W 11 lks, tree down, with both faces in evidence; and S68° E 22 lks, stump in place with lower face in evidence. Found Wood Post 1 3/4 chains West and 2 chains North of True Corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buchler*
BILLY D. BUCHLER
REGISTERED LAND SURVEYOR

DATE 7/29/1964