

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N. R. 28W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 29-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4/22/64

WITNESSES TO CORNER..... 12" Soft Maple ($\frac{1}{4}$ S NBT) S61° W 47 lks.



8" Soft Maple ($\frac{1}{4}$ S NBT) S25° E 25½ lks.

Corner lies on North edge of swamp.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from remains of two Original B.T.s. A Yellow Pine Stump with Notch of witness mark evident, Stump badly burned, bearing E56° W 20 lks., and a Cedar S58°E 42 lks., down and in very poor condition.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 7/29/1964