

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>28W</u>	<u>E10</u>
	T _____ R _____	<u>F9</u>
	T _____ R _____	<u>H9</u>
	T _____ R _____	
2. Property Controlling in Section	S <u>29</u> T _____ R _____	<u>14</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

10-6-89 90

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on August 15, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	28	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E10	F9	H9	14
Original monument and accessories not found.	Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E10	F9	H9	14
Restored midway and on line.	Restored midway and on line.	Restored midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E10	F9	H9	14
Set 1" ID x 36" IP with 4" aluminum cap.	Set 1" ID x 36" IP with 4" aluminum cap.	Set 1" ID x 32" IP with 4" aluminum cap.	Set 1" ID x 32" IP with 4" aluminum cap.
10" spruce N30E 6.0' 1/4S, NBT	3" sugar S22E 27.7' 1/4S, NBT	6" balsam N60W 8.4' 1/4S, NBT	5" balsam S78W 82.7' 1/16S, BT
4" sugar maple S01E 10.9' 1/4S, NBT	5" sugar S11W 38.9' 1/4S, NBT	8" balsam S48E 24.3' 1/4S, NBT	5" balsam S33E 52.8' 1/16S, BT
7" sugar maple S65W 10.9' 1/4S, NBT	4" elm S55W 43.2' 1/4S, NBT	6" balsam S22E 19.4' 1/4S, NBT	5" cedar S23W 95.9' 1/16S, BT

Signed by Keith Sackett Date 9-21-89

Surveyor's Michigan License No. 19006