

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
 Marquette

(County)	Located In:	Corner Code #
1 Public Land Survey	T 45N R 28W	B9
	T R	E9
	T R	
	T R	
2 Property Controlling in Section	S 20 T R	B
	S 27 T R	2
3 Miscellaneous Property in Sec.	S T R	
	S T R	

*15-6 E 7  
 15-6 W*

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith Sackett, in a field survey on August 15, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<u>B9</u>	<u>E9</u>	<u>B</u>	<u>2</u>
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>B9</u>	<u>E9</u>	<u>B</u>	<u>2</u>
Restored midway and on line.	Restored by double proportion.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>B9</u>	<u>E9</u>	<u>B</u>	<u>2</u>
Set 1" x 32" IP with plastic cap.	Set 1" 10 x 32" IP with 4" aluminum cap.	Set 1" 10 x 32" IP with 4" aluminum cap.	Set 1" 10 x 36" IP with 4" aluminum cap.
10" white pine S10W 16.7' 1/4S NBT	5" maple N44W 71.4' S20, NBT	10" maple S60W 1.8' 1/16S, BT	4" cedar N02E 7.5' 1/16S, BT
4" maple N86W 2.9' 1/4S NBT	14" oak S61E 46.0' S20, NBT	4" maple N66E 45.6' 1/16S, BT	6" cedar S75E 0.3' 1/16S, BT
8" white birch N68E 2.0' 1/4S NBT	10" oak N04E 108.5' S21, NBT	10" maple S02E 2.1' 1/16S, BT	5" cedar S66W 4.4' 1/16S, BT

Signed by Keith Sackett Date 9-21-89  
 Surveyor's Michigan License No. 19006