

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
 County

	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>28W</u>	<u>08</u>
	T _____ R _____	<u>08</u>
	T _____ R _____	<u>09</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T _____ R _____	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Handwritten notes:
 10
 12
 16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on August 10, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	31	32	33	34	35	36						
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

08	09	09	12
Not set on original survey nor subsequently, apparently.	Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

08	09	09	12
Established at intersection of 1/4 lines.	Restored midway and on line.	Restored on E-W proportion supported by old pine stump.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate the position of the corner:

08	09	09	12
Set 1" 10 x 36" IP with 4" aluminum cap.	Set 1" x 36" IP with 4" aluminum cap.	Set 1" 10 x 32" IP with 4" aluminum cap.	Set 1" 10 x 32" IP with 4" aluminum cap.
6" maple N15W 32.0' 1/4S, BT	10' tamarack N70E 0.1' 1/4S, NBT	5" maple 80SE 7.3' S27, NBT	5" oak N24W 4.7' 1/16S BT
9" white birch N58E 28.7' 1/4S, BT	10' cedar S67W 14.2' 1/4S, NBT	7" maple N52E 8.0' S22, NBT	9" oak S45E 12.0' 1/16S BT
5" aspen S72W 26.1' 1/4S BT	11' tamarack N14W 9.6' 1/4S, NBT	8" maple S88W 23.9' S28, NBT	6" oak S64W 12.8' 1/16S BT

Signed by Keith Sackett Date 9-21-89

Surveyor's Michigan License No. 19006