

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T Marquette
 (County)

Located In:

Corner Code --#

1. Public Land Survey	T 45N R 28W	D3
	T R	E3
	T R	
	T R	
2. Property Controlling in Section	S 8 T R	12
	S T R	13
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **Keith Sackett**, in a field survey on **March 12**, 19 **90**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5		*										
6	16	17	18	15	14	13						
7												
8	15	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A Description of original monument and accessories and/or subsequent restoration:

D3	E3	12	13
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D3	E3	12	13
Restored midway and on line.	Restored by proportion and land calls.	Established during section subdivision.	Established during section subdivision.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D3	E3	12	13
Set 1" ID x 32" iron pipe v/plastic cap.	Set 1" ID x 32" iron pipe v/plastic cap.	Set 1" ID x 32" iron pipe v/plastic cap.	Set 1" ID x 32" iron pipe v/plastic cap.
12" spruce S09W 11.2' 1/4s, NBT	4" spruce N69E 11.9' s4, NBT	12" j. pine N80E 53.1' 1/16s, BT	5" r. pine S39W 1.0' 1/16s, BT
6" spruce N45E 11.5' 1/4s, NBT	4" spruce S08E 8.9' s9, NBT	4" maple N46W 35.5' 1/16s, BT	6" j. pine N56E 5.5' 1/16s, BT
4" spruce N18W 7.7' 1/4s, NBT	7" cedar N34W 32.8' s5, NBT	4" maple S70W 32.8' 1/16s, BT	12" j. pine S82E 16.2' 1/16s, BT

Signed by Keith Sackett Date August 27, 1990
 Surveyor's Michigan License No 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 70, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983