

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located in:

Corner Code #

1. Public Land Survey

T.45N R. 28W

D13

T.45N R. 28W

G13

T. R.

T. R.

2. Property Controlling in Section

S. T. R.

S. T. R.

3. Miscellaneous Property in Sec.

S. T. R.

S. T. R.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

May 22 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(D13) Quarter corner common to Section 5 T44N-R28W and Section 32 T45N-R28W. Reestablished midway and on line between Section corners in 1959 by Billy D. Buckler RLS. 1" pipe with 4" brass cap. 8" W. Birch S40E 03 links, 6" H. Maple N62W 69 links.

(G13) Section corner common to Sections 3-4 T44N-R28W and 33-34 T45N-R28W. Reestablished using proportionate measurement by Billy D. Buckler RLS, in 1959. 1" pipe with 4" brass cap. 24" W.Pine S22E 310 links, 20" Red Pine S86W 257 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(D13) Recovered the 1959 monument disturbed, laying on the ground at the corner position. It was probably removed by logging equipment. Found the monument's ground hole at record bearing and distance from the decaying stump remains of both of the 1959 NBTs and replaced the monument at that position.

(G13) Recovered the 1959 monument as described, leaning. Straightened the monument and set at record bearing and distance from the two 1959 NBTs, now both stumps with iron marks visible. The cap on this monument is incorrectly stamped R29W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D13) 1" ID iron pipe with 4" brass cap. Blazed and scribed:
5" Poplar N56E 13.2' "1/4S NBT"
7" Poplar S34E 20.5' do
4" Poplar S31W 8.8' do
2" Maple in clump N78W 38.8' do
Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.

(G13) 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:
11" Maple N73E 36.4' "S34 NBT"
5" Tamarack S04E 43.5' "S3 NBT"
4" W.Spruce S35W 37.0' "S4 NBT"
15" W.Spruce N36W 49.5' "S33 NBT"
Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 8/8/01

For the Michigan Department of Natural Resources - Forest Management Division