

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>28W</u>	<u>E13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 22 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (E13) Corner common to Sections 4-5 T44N-R28W and 32-33 T45N-R28W. Reestablished using proportionate measurement by Billy D. Buckler RLS, in 1959. 1" iron pipe with 4" brass cap. 9" B.Spruce N43E 10 links, 8" B.Spruce S02W 15 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E13) Recovered the 1959 monument, as described, in good condition, projecting about 3' a.g., and at record bearing and distance from the remains of the B.Spruce NBT NE, now a decayed stump with no markings visible. The NBT south has been uprooted but is close to record bearing and distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E13) 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:  
 6" Balsam N17E 19.9' "S33 NBT"  
 4" Balsam S61E 14.3' "S4 NBT"  
 7" B.Spruce S45E 56.4' "S4 NBT"  
 6" Balsam S12W 18.0' "S5 NBT"  
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/8/01

For the Michigan Department of Natural Resources - Forest Management Division