

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY
T 45N R 29W

DESCRIPTION OF CORNER South 1/16 corner on N & S 1/4 line of Section 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 18, 1972

WITNESSES TO CORNER..... B. Spruce 5 N73°E (mag.) 6.9 ft. "1/16S, BT"



B. Spruce 7 S19½°E (mag.) 12.4 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established on line between S 1/4 corner 19.989 ch. S and
Center 1/4 corner 19.989 ch. N.

This corner was not established in original survey nor subsequently,
apparently.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

Marquette County Road Commission
District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 20, 1972

R 4047
Rev. 1/72