

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY
T 45N R 29W

DESCRIPTION OF CORNER East 1/16 corner between Sections 24 and 25

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED November 5, 1971

WITNESSES TO CORNER..... R. Pine 20 N48°W (mag.) 54.2 ft. "1/16S, BT"



J. Pine 4 N85°E (mag.) 14.7 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner not established in original survey nor subsequently, apparently. Corner established on line between section corner 19.784 ch. E and 1/4 corner 19.784 ch. W.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

Marquette County Road Commission
District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 20, 1972

R 4047
Rev. 1/72