

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MARQUETTE

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45 N. R. 29 E. W.	L9
2. PROPERTY CONTROLLING IN SECTION _____	24, T. 45 N. R. 29 E. W.	5, 12, & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner L9: Spruce post (Not found. No subsequent monuments found.)
 W. Birch 10 S65E 15 " " " " accessory "
 Spruce 10 N65W 13 " " " " " "

Corners 5, 12, & 16: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L9: Re-established 10/10/71 on line between sec. corners 39.568 ch. to E and to W.
 Corner 5: Established 6/1/73 on line between Center 1/4 cor. 19.954 ch. S and N 1/4 corner 19.954 ch. N.
 Corner 12: Established 5/31/73 on line between Center 1/4 corner 20.003 ch. N and S 1/4 cor. 20.003 ch. S.
 Corner 16: Established 11/5/71 on line between sec. cor. 19.784 ch. E and 1/4 cor. 19.784 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for Corners L9, 12, & 16: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Monument for Corner 5: 4"x4"x5 1/2' squared cedar post, scribed "1/16".
 Witnesses for Corner L9: Cedar 8 S29°W (mag.) 100.6 ft. "1/4S, NBT"
 W. Pine 7 N 6°E (mag.) 40.8 ft. "1/4S, NBT"
 Witnesses for Corner 5: W. Spruce 12 S49°W (mag.) 41.8 ft. "1/16S, BT"
 W. Birch 8 N10°W (mag.) 21.0 ft. "1/16S, BT"
 Witnesses for Corner 12: B. Spruce 5 N76°E (mag.) 6.4 ft. "1/16S, BT"
 B. Spruce 7 S21°E (mag.) 13.2 ft. "1/16S, BT"
 Witnesses for Corner 16: R. Pine 20 N48°W (mag.) 54.2 ft. "1/16S, BT"
 J. Pine 4 N85°E (mag.) 14.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 7, 1973

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

