

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY
T 45N R 29W

DESCRIPTION OF CORNER Center of Section 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 18, 1972

WITNESSES TO CORNER..... J. Pine 7 N38½°W (mag.) 11.3 ft. "1/4S, BT"



J. Pine 4 S33°E (mag.) 6.3 ft. "1/4S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously, except approximately. Corner established at intersection of quarterlines. Found a 1" squared stake or chainage marker S19°E 33 lks. and a fence corner N88°E 1.385 ch. from corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

Marquette County Road Commission
District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 18, 1972

R 4047
Rev. 1/72