

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>29</u> XX R. <u>W.</u>	L 8 & M6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner L 8:** Not established in original survey nor subsequently, except by approximation. Found a 1" squared picket S20°E 36½ lks., and a fence corner N89°E 1.403 ch.
- Corner M 6:** Yellow Birch post (Not found)
 W. Pine 14 N56E 34 (Found)
 Y. Pine 16 S70W 17 "

Found a 6' length of narrow gauge iron rail near W. Pine BT.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner L 8:** Established 5/31/73 at intersection of quarter lines.
- Corner M 6:** Corner monumented 5/15/73 from two original BT stumps, both burned and in poor condition, but with recognizable lower blazes and axe notches. Both stumps agree with recorded originals in species, absolute and relative size, and distance and bearing to corner. Position shows substantial agreement with original corners 1½ miles to N and to S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for both corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner L 8:** J. Pine 7 N41°W (mag.) 9.9 ft. "1/4S, BT"
 J. Pine 4 S26°E (mag.) 7.9 ft. "1/4S, BT"
- Witnesses for Corner M 6:** R. Pine 21 S15°W (mag.) 9.1 ft. "1/4S, NBT"
 R. Maple 5 N23°E (mag.) 16.1 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 7, 1973

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581