

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45N N. R. 29 E. V.	L 7
2. PROPERTY CONTROL- ING IN SECTION 24 _____	T. 45 N. R. 29 E. V.	1 & 8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. V.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner L 7: Maple post (not found) No subsequent monuments found.**  
 S. Pine 6 S70W 18 (not found)  
 S. Pine 7 N75E 22 (found)

**Corner 1 & 8. Not established in original survey nor subsequently, apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner L 7: Corner recovered from stump of original BT shown above. Stump has remnant of lower blaze and notch, no scribe marks. Corner falls almost exactly at midpoint on line between Sec. Corners E and W. Fence corner lies S58°E 1.42 chains. Monument placed on October 26, 1971.**  
**Corner 1: Established 10/26/71 on line between Sec. Cor. 19.738 ch. W and 1/4 cor. 19.738 ch. E.**  
**Corner 8: Established 5/18/72 on line between Center 1/4 corner 19.761 ch. E and W 1/4 corner 19.761W. Found a 3/4" iron pipe N53°E 1.10 ch. for an approximate corner.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**  
**Witnesses for Corner L 7: W. Pine 12 S10°W (mag.) 5.2 ft. "1/4S, NBT"**  
**W. Pine 6 S58°E (mag.) 25.4 ft. "1/4S, NBT"**  
**Also squared and scribed an 8" J. Pine 5 lks. N of pipe.**  
**Witnesses for Corner 1: W. Pine 6 S55°W (mag.) 29.6 ft. "1/16S, BT"**  
**Cedar 6 S89°E (mag.) 28.6 ft. "1/16S, BT"**  
**Witnesses for Corner 8: B. Spruce 6 N29°W (mag.) 12.4 ft. "1/16S, BT"**  
**B. Spruce 6 N50°E (mag.) 11.5 ft. "1/16S, BT"**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 19, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581