

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MARQUETTE

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. EX R. 29 EX W.	L 7
2. PROPERTY CONTROL- ING IN SECTION 24	T. 45 N. EX R. 29 EX W.	1 & 8
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner L 7: Maple Post (Not found. No subsequent monuments found)
 S. Pine 6 S70W 18 (Not found)
 S. Pine 7 N75E 22 (Found)

Corners 1 & 8: Not established in original survey nor subsequently, apparently, except found a 3/4" iron pipe approx. cor. N53°E 1.10 ch. from Corner 8.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L 7: Corner recovered from stump of original BT shown above. Stump has remnant of lower blaze and notch, no scribe marks. Fence corner lies S58°E 1.42 ch. Monument placed on October 26, 1971.
 Corner 1: Established 10/26/71 on line between Sec. Cor. 19.738 ch. W and 1/4 corner 19.738 ch. E.
 Corner 8: Established 6/1/73 on line between Center 1/4 cor. 19.760 ch. E and W 1/4 corner. 19.760 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Witnesses for Corner L7: W. Pine 12 S10°W 5.2 ft. "1/4S, NBT"
 W. Pine 6 S58°E 25.4 ft. "1/4S, NBT"
 Also squared and scribed an 8" J. Pine 5 lks. N. of pipe.
 Witnesses for Corner 1: W. Pine 6 S55°W 29.6 ft. "1/16S, BT"
 Cedar 6 S89°E 28.6 ft. "1/16S, BT"
 Witnesses for Corner 8: B. Spruce 6 N29°W 11.6 ft. "1/16S, BT"
 B. Spruce 6 N50°E 10.8 ft. "1/16S, BT"
 Also squared and scribed a 3" B. Spruce S42°E 3.7 ft. from pipe.
 All bearings magnetic.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 7, 1973

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

